



REPORT



December 29, 1989

Mr. Fred Estilo
Public Works Center, Bldg. 1-A
Great Lakes Naval Training Center
Great Lakes, IL 60088

RE: Contract N62472087-C-7706
Harbor Material Analysis

Dear Mr. Estilo:

STS Consultants, Ltd. has completed collection and analysis of harbor sediment samples at the above-referenced project. The project location is illustrated on Figure 1. The scope of work consisted of collecting continuous sediment samples for five feet from the harbor bottom at seven locations designated by the Public Works Center (PWC), homogenizing and preserving the sample, and analyzing each sample for parameters designated by the PWC. This letter report summarizes the method of analysis and results obtained.

Subsurface Exploration

A barge-mounted tripod drilling unit was used to recover core samples to a minimum depth of five feet into the harbor sediments. Boring locations were marked by buoys and located by land survey from marina structures. The boring locations are illustrated on Figure 2 in Appendix A.

Continuous sediment samples were recovered from each boring location using Osterberg, Shelby Tube, and lined Split Barrel samplers, depending upon the subsurface conditions encountered. The first foot of frozen soil at borings B-202 and B-203 (located on the sand bar in the boat basin) was broken and sampled with a hand shovel.

Samples were sealed in Shelby tubes, split barrel liners, and clean sample jars and were returned to the STS geotechnical laboratory.

A background water sample was collected from Lake Michigan south of the south breakwater. The sample was placed in containers supplied by the subcontract laboratory, and preserved by refrigeration to 4°C.

STS Consultants Ltd.
Consulting Engineers

111 Pfingsten Road
Northbrook, Illinois 60062
708.272.6520/Fax 708.498.2721



Great Lakes Naval Training Center
STS Project No. 25123-XH
December 29, 1989
Page 2

Sample Handling

Small representative portions of each sample were placed in clean sample jars for visual classification and water content tests. The remaining portions of each sample corresponding to the required five foot length were combined. Sediment samples were trimmed where necessary to eliminate sample overlap and excess core length from the prepared soil samples. Each five foot core was homogenized using a mechanical mixer and split into two samples for mechanical and chemical analysis.

The samples to undergo chemical analysis were placed into clean containers supplied by the subcontract laboratory and preserved by refrigeration to 4°C. Soil and background water samples were delivered to the subcontract laboratory. Samples which were used for the mechanical analysis samples were sealed in clean sample containers.

Soils Laboratory Analysis

The results of the visual classification and water content tests performed on each sample are presented on the boring logs included in Appendix A.

A particle size analysis was performed on each composite soil sample in accordance with the Illinois Environmental Protection Agency (IEPA) Water Quality Certification Section 401 Permit requirements. The results of this test are summarized on Table 1, and are reported as the percentage by weight passing the No. 230 U.S. sieve. In four samples (B-201, B-204, B-205, and B-206) the percent passing the No. 230 sieve exceeded 20%, which is the criteria used by the IEPA for additional chemical analysis requirements. The particle size laboratory results are included in Appendix B.

Chemical Laboratory Analysis

Supernatant tests were performed on each composite sample in accordance with 208(f) of Standard Methods for Water and Wastewater Analysis (14th ed., 1975). Fifteen compounds were measured after 0 and 15 minute settling periods in accordance with the scope of work outlined by the PWC. The results of these tests are summarized on Table 2. In addition, each composite sample was tested for total organic carbon, total solids, PCBs, and 14 polynuclear aromatic hydrocarbon compounds. These test results are summarized on Table 3. Detailed results are provided in the subcontract laboratory report included in Appendix C.

For comparison purposes, the IEPA measures supernatant test results against the levels specified in the Illinois Administrative Code, Title 35 - Environmental Protection; Subtitle C - Water Pollution; Chapter 1 - Pollution Control Board; Subparts B, C, and E to determine if the Lake Michigan water quality will be impacted adversely by the



Great Lakes Naval Training Center
STS Project No. 25123-XH
December 29, 1989
Page 3

addition of the sediment. Subparts B, C, and E list the maximum allowable concentrations of certain chemical constituents for general use water, public and food processing water supplies, and Lake Michigan water, respectively. Since test methods for these water quality standards have not been established, it should be noted that a direct correlation with supernatant test results is not advisable. Instead, the standards are used as a general guideline for purposes of comparison. Maximum allowable concentrations under the three subparts (as amended through May 4, 1989) for the constituents analyzed under the supernatant testing are shown on Table 2.

Results


As shown on Table 2, many of the metals tested in the supernatant analysis exceed the general use and public water quality standards, even after the 15 minute settling period. Many polynuclear aromatic hydrocarbon compounds were detected in each sample, although some of the lower concentrations may not be significant (as explained in Appendix C). One PCB compound was detected in sample B-204.

It is recommended that the PWC contact the IEPA and the United States Environmental Protection Agency (USEPA) to discuss the results and the feasibility of open water disposal of dredged material.

It has been a pleasure to work with you on this project. If you have any questions or comments, or need additional information, please feel free to call at (708) 272-6520.

Sincerely,

STS CONSULTANTS, LTD.



Linda M. Burke, P.E.
Senior Project Engineer


Andrew E. Haubert, P.E.
Principal Engineer

LMB/th

LMB98

STS Project No. 25123-XF



STS Consultants Ltd.
Consulting Engineers

PROJECT/CLIENT

VICINITY MAP

HARBOR MATERIAL ANALYSIS

GREAT LAKES NAVAL TRAINING CENTER

DRAWN BY

CHECKED BY

APPROVED BY

SCALE
1" = 2000'

STS DRAWING NO.

MMW

LMB

FIGURE NO. 1

25123-XF

Table 1

Harbor Material Analysis
Great Lakes Naval Training Center
Particle Size Distribution Test Results
Job Number 25123-XF

| Sample ID | Percent (by weight) passing No. 230 U.S. sieve |
|-----------|--|
| B-201 | 58.8 |
| B-202 | 5.5 |
| B-203 | 16.6 |
| B-204 | 72.9 |
| B-205 | 95.0 |
| B-206 | 55.2 |
| B-207 | 17.3 |

Table 2

Harbor Material Analysis
Great Lakes Naval Training Center

Supernatant Test Results
Job Number 25123-XF

| Parameter | Units | B-201 | | B-202 | | B-203 | | B-204 | |
|---------------|-------|-------|--------|-------|--------|-------|--------|-------|--------|
| | | 0 min | 15 min | 0 min | 15 min | 0 min | 15 min | 0 min | 15 min |
| Silver | mg/l | 0.304 | 0.248 | 0.043 | 0.034 | 0.069 | 0.067 | 0.390 | 0.429 |
| Arsenic | ug/l | 1098 | 1074 | 212 | 216 | 478 | 448 | 1560 | 2370 |
| Beryllium | mg/l | 0.05 | 0.04 | ND | ND | 0.04 | 0.04 | 0.10 | 0.10 |
| Cadmium | mg/l | 0.123 | 0.098 | 0.054 | 0.064 | 0.104 | 0.104 | 0.951 | 1.22 |
| Total Cyanide | ug/l | ND | ND | 104 | 93 | 81 | 74 | 1450 | 580 |
| Chromium | mg/l | 1.35 | 1.48 | 0.449 | 0.501 | 0.735 | 0.695 | 5.19 | 6.10 |
| Hex. Chromium | mg/l | ND | ND | ND | ND | ND | ND | ND | ND |
| Copper | mg/l | 3.91 | 3.85 | 4.73 | 5.12 | 9.12 | 9.24 | 59.9 | 85.1 |
| Mercury | ug/l | ND | 1.4 | 6.9 | 8.4 | 14.6 | 38.4 | 235.0 | 99.0 |
| Nickel | mg/l | 2.49 | 2.33 | 1.39 | 1.47 | 2.00 | 2.07 | 14.5 | 23.2 |
| Lead | mg/l | 5.7 | 5.4 | 3.3 | 3.7 | 11 | 11 | 68 | 50 |
| Antimony | ug/l | ND | ND | 3.0 | 2.3 | 8.0 | 6.5 | 43.5 | 70.2 |
| Selenium | ug/l | 18.0 | 14.8 | 8.2 | 9.3 | 17.9 | 25.2 | 138 | 147 |
| Thallium | mg/l | 1.8 | 1.23 | ND | ND | 0.2 | 0.19 | 1.12 | 1.24 |
| Zinc | mg/l | 9.92 | 11 | 16.4 | 18.3 | 35.0 | 35.2 | 137 | 195 |

| Parameter | Units | B-205 | | B-206 | | B-207 | | Lake Michigan Water | Regulatory Limit and Subpart |
|---------------|-------|-------|--------|-------|--------|-------|--------|---------------------|------------------------------|
| | | 0 min | 15 min | 0 min | 15 min | 0 min | 15 min | | |
| Silver | mg/l | 0.441 | 0.062 | 0.362 | 0.098 | 0.108 | 0.017 | ND | 0.005 B |
| Arsenic | ug/l | 2860 | 288 | 2990 | 786 | 538 | 118 | ND | 50 C (various) |
| Beryllium | mg/l | 0.06 | 0.03 | 0.07 | 0.03 | 0.04 | ND | ND | NR |
| Cadmium | mg/l | 0.367 | 0.024 | 0.411 | 0.094 | 0.116 | 0.011 | ND | 0.01 C |
| Total Cyanide | ug/l | 115 | 92 | 68 | 128 | 42 | 52 | ND | 25 B |
| Chromium | mg/l | 6.72 | 1.57 | 4.72 | 1.49 | 0.910 | 0.218 | ND | 0.05 C |
| Hex. Chromium | mg/l | ND | ND | ND | ND | ND | ND | ND | 0.05 B |
| Copper | mg/l | 20.4 | 2.10 | 27.6 | 6.58 | 20.5 | 5.00 | ND | 0.02 BE |
| Mercury | ug/l | 30.2 | 5.2 | 17.8 | 7.4 | 2.1 | 1.8 | ND | 0.5 B |
| Nickel | mg/l | 5.58 | 0.64 | 4.00 | 0.85 | 1.03 | 0.19 | ND | 1.0 B |
| Lead | mg/l | 40 | 4.2 | 30 | 6.8 | 13 | 3.0 | ND | 0.05 C |
| Antimony | ug/l | 5.2 | ND | 16.8 | 10.0 | 24.7 | 11.0 | ND | NR |
| Selenium | ug/l | 93.0 | 8.4 | 48.0 | 8.2 | 9.9 | ND | ND | 0.01 C |
| Thallium | mg/l | 1.46 | ND | 1.63 | 0.27 | 0.47 | ND | ND | NR |
| Zinc | mg/l | 56.5 | 5.62 | 12.4 | 49.6 | 35.4 | 8.02 | 0.05 | 1.0 B |

Note: "ND" denotes concentrations below detection limits.

"NR" denotes compounds not regulated under Subparts B, C, and E.

Table 3

Harbor Material Analysis
Great Lakes Naval Training Center

Chemical Test Results
Job Number 25123-XF


| Parameter | Units | B-201 | B-202 | B-203 | B-204 | B-205 | B-206 | B-207 |
|------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| Total Organic Carbon | mg/kg | 11900 | 1190 | 2530 | 12300 | 1570 | 13300 | 10700 |
| Total Solids | % | 81.4 | 80.9 | 79.6 | 63.0 | 59.5 | 73.9 | 82.0 |
| PCB: | | | | | | | | |
| PCB-1016 | ug/kg | ND | ND | ND | ND | ND | ND | ND |
| PCB-1221 | ug/kg | ND | ND | ND | ND | ND | ND | ND |
| PCB-1232 | ug/kg | ND | ND | ND | ND | ND | ND | ND |
| PCB-1242 | ug/kg | ND | ND | ND | ND | ND | ND | ND |
| PCB-1248 | ug/kg | ND | ND | ND | ND | ND | ND | ND |
| PCB-1254 | ug/kg | ND | ND | ND | 2400 | ND | ND | ND |
| PCB-1260 | ug/kg | ND | ND | ND | ND | ND | ND | ND |
| PAH: | | | | | | | | |
| Acenaphthene | ug/kg | ND | ND | ND | ND | ND | ND | ND |
| Acenaphthylene | ug/kg | ND | ND | ND | ND | ND | ND | ND |
| Anthracene | ug/kg | ND | ND | ND | ND | ND | ND | ND |
| Benz(a)anthracene | ug/kg | 560 | 270 | 500 | 1100 | 180 | 740 | 550 |
| Benzo(b)fluoranthene | ug/kg | 570 | 260 | 540 | 740 | 200 | 260 | 620 |
| Benzo(g,h,i)perylene | ug/kg | 250 | 160 | 310 | 680 | 150 | 370 | 320 |
| Benzo(a)pyrene | ug/kg | 310 | 92 | 360 | 810 | 190 | 1300 | 360 |
| Chrysene | ug/kg | 620 | 360 | 670 | 1800 | 310 | 770 | 580 |
| Dibenz(a,h)anthracene | ug/kg | 98 | 55 | 110 | 260 | 47 | 170 | 110 |
| Fluoranthrene | ug/kg | 170 | ND | 170 | 450 | ND | ND | 130 |
| Fluorene | ug/kg | 120 | ND | ND | 266 | ND | ND | ND |
| Indeno(1,2,3,cd)pyrene | ug/kg | 780 | 630 | 190 | 704 | 720 | 250 | 800 |
| Phenanthrene | ug/kg | 850 | 410 | 770 | 2100 | ND | 650 | 600 |
| Pyrene | ug/kg | 830 | 450 | 970 | 2100 | 340 | 910 | 630 |

Note: "ND" denotes concentrations below detection limits.



A

[illegible]



STS Consultants Ltd.
Consulting Engineers

FIGURE 2
BORING LOCATION DIAGRAM
GREAT LAKES NAVAL TRAINING CENTER
HARBOR MATERIAL ANALYSIS
GREAT LAKES, ILLINOIS

| DRAWN BY | DATE | SCALE | STS PROJECT NO. |
|------------|----------|-----------|-----------------|
| KKB | 12-19-89 | 1"=200' | 25123-XF |
| CHECKED BY | DATE | SHEET NO. | STS FILE NO. |
| LMB | 12-19-89 | | 25123-XF |



STS Consultants Ltd.

OWNER

Great Lakes Naval Training Center

PROJECT NAME

Harbor Material Analysis

LOG OF BORING NUMBER

B-201

ARCHITECT-ENGINEER


SITE LOCATION

Great Lakes, Illinois

| DEPTH (FT) ELEVATION (FT) | SAMPLE NO. | SAMPLE TYPE | SAMPLE DISTANCE RECOVERY | DESCRIPTION OF MATERIAL | UNIT DRY WT. LBS./FT. ³ | UNCONFINED COMPRESSIVE STRENGTH TONS/FT. ² | | | | | PLASTIC LIMIT % | | | | | WATER CONTENT % | | | | | LIQUID LIMIT % | | | | | STANDARD PENETRATION BLOWS/FT. | | | | |
|------------------------------|------------|-------------|-----------------------------|--|---------------------------------------|--|---|---|---|---|-----------------|----|----|----|----|-----------------|----|----|----|----|----------------|----|----|----|----|-----------------------------------|----|----|----|----|
| | | | | | | 1 | 2 | 3 | 4 | 5 | 10 | 20 | 30 | 40 | 50 | 10 | 20 | 30 | 40 | 50 | 10 | 20 | 30 | 40 | 50 | 10 | 20 | 30 | 40 | 50 |
| 2.5 | | | | Water | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | 1 | OS | | Fine to medium sand, trace silt - brownish gray - saturated (SP) | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7.5 | 2 | OS | | Silt - gray - saturated (ML) | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9.5 | 3 | SS | | Sandy silt - gray saturated (ML) Note: Sample 3 recovered from 7.4 to 9.5' at 2' offset | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | END OF BORING | | | | | | | | | | | | | | | | | | | | | | | | | | |

THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES: IN-SITU, THE TRANSITION MAY BE GRADUAL.

| | | | | | |
|----|----------|----------------|--------------------|-------------|---------------|
| WL | WS OR WD | BORING STARTED | 12/6/89 | STS OFFICE | Northbrook-01 |
| WL | BCR | ACR | BORING COMPLETED | DRAWN BY | KKB |
| WL | | RIG | Tripod and Cathead | APP'D BY | LMB/nt |
| | | FOREMAN | Jack | SHEET NO. | 1 OF 1 |
| | | | | STS JOB NO. | 25123-XF |



Harbor Material Analysis

ARCHITECT-ENGINEER

Great Lakes, Illinois

BLOWS/FT.

END OF BORING

THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES: IN-SITU, THE TRANSITION MAY BE GRADUAL.

25123-XF



STS Consultants Ltd.

OWNER

Great Lakes Naval Training Center

PROJECT NAME

Harbor Material Analysis

LOG OF BORING NUMBER

B-203

ARCHITECT-ENGINEER

SITE LOCATION

Great Lakes, Illinois

| DEPTH (FT) ELEVATION (FT) | SAMPLE NO. | SAMPLE TYPE | SAMPLE DISTANCE RECOVERY | DESCRIPTION OF MATERIAL | UNIT DRY WT. LBS./FT. ³ | PLASTIC LIMIT % | | | | | WATER CONTENT % | | | | | LIQUID LIMIT % | | | | |
|------------------------------|------------|-------------|-----------------------------|---|---------------------------------------|-----------------|----|----|----|----|----------------------|----|----|----|--|----------------|--|--|--|--|
| | | | | | | X-----●-----△ | | | | | STANDARD PENETRATION | | | | | BLOWS/FT. | | | | |
| 10 | 20 | 30 | 40 | 50 | 10 | 20 | 30 | 40 | 50 | 10 | 20 | 30 | 40 | 50 | | | | | | |
| 1 | Shovel | | | Fine to medium sand, trace gravel and coarse sand - gray saturated (SP) | | | | | | | | | | | | | | | | |
| 2.5 | 2 | ST | | Silty fine to medium sand, trace gravel - gray - saturated (SM) | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | |
| 6.5 | | | | END OF BORING | | | | | | | | | | | | | | | | |

THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES: IN-SITU, THE TRANSITION MAY BE GRADUAL.

| | | | | | |
|----|----------|----------------|--------------------|-------------|---------------|
| WL | WS OR WD | BORING STARTED | 12/6/89 | STS OFFICE | Northbrook-01 |
| WL | BCR | ACR | BORING COMPLETED | DRAWN BY | KKB |
| WL | | RIG | Tripod and Cathead | FOREMAN | Jack |
| | | | | APP'D BY | LMB/nt |
| | | | | SHEET NO. | 1 OF 1 |
| | | | | STS JOB NO. | 25123-XF |



Harbor Material Analysis

ARCHITECT-ENGINEER

Great Lakes, Illinois

DESCRIPTION OF MATERIAL

SURFACE ELEVATION

Water

Clayey silt - gray - saturated (ML) Note: Trace roots in sample 3

END OF BORING

| UNCONFINED COMPRESSIVE STRENGTH TONS/FT. ² |
|--|
|--|

1 2 3 4 5

| PLASTIC | WATER | LIQUID |
|---------|-------|--------|
| 1 | 2 | 3 |
| 4 | 5 | 6 |
| 7 | 8 | 9 |
| 10 | 11 | 12 |
| 13 | 14 | 15 |
| 16 | 17 | 18 |
| 19 | 20 | 21 |
| 22 | 23 | 24 |
| 25 | 26 | 27 |
| 28 | 29 | 30 |
| 31 | 32 | 33 |
| 34 | 35 | 36 |
| 37 | 38 | 39 |
| 40 | 41 | 42 |
| 43 | 44 | 45 |
| 46 | 47 | 48 |
| 49 | 50 | 51 |
| 52 | 53 | 54 |
| 55 | 56 | 57 |
| 58 | 59 | 60 |
| 61 | 62 | 63 |
| 64 | 65 | 66 |
| 67 | 68 | 69 |
| 70 | 71 | 72 |
| 73 | 74 | 75 |
| 76 | 77 | 78 |
| 79 | 80 | 81 |
| 82 | 83 | 84 |
| 85 | 86 | 87 |
| 88 | 89 | 90 |
| 91 | 92 | 93 |
| 94 | 95 | 96 |
| 97 | 98 | 99 |
| 100 | 101 | 102 |
| 103 | 104 | 105 |
| 106 | 107 | 108 |
| 109 | 110 | 111 |
| 112 | 113 | 114 |
| 115 | 116 | 117 |
| 118 | 119 | 120 |
| 121 | 122 | 123 |
| 124 | 125 | 126 |
| 127 | 128 | 129 |
| 130 | 131 | 132 |
| 133 | 134 | 135 |
| 136 | 137 | 138 |
| 139 | 140 | 141 |
| 142 | 143 | 144 |
| 145 | 146 | 147 |
| 148 | 149 | 150 |
| 151 | 152 | 153 |
| 154 | 155 | 156 |
| 157 | 158 | 159 |
| 160 | 161 | 162 |
| 163 | 164 | 165 |
| 166 | 167 | 168 |
| 169 | 170 | 171 |
| 172 | 173 | 174 |
| 175 | 176 | 177 |
| 178 | 179 | 180 |
| 181 | 182 | 183 |
| 184 | 185 | 186 |
| 187 | 188 | 189 |
| 190 | 191 | 192 |
| 193 | 194 | 195 |
| 196 | 197 | 198 |
| 199 | 200 | 201 |
| 202 | 203 | 204 |
| 205 | 206 | 207 |
| 208 | 209 | 210 |
| 211 | 212 | 213 |
| 214 | 215 | 216 |
| 217 | 218 | 219 |
| 220 | 221 | 222 |
| 223 | 224 | 225 |
| 226 | 227 | 228 |
| 229 | 230 | 231 |
| 232 | 233 | 234 |
| 235 | 236 | 237 |
| 238 | 239 | 240 |
| 241 | 242 | 243 |
| 244 | 245 | 246 |
| 247 | 248 | 249 |
| 250 | 251 | 252 |
| 253 | 254 | 255 |
| 256 | 257 | 258 |
| 259 | 260 | 261 |
| 262 | 263 | 264 |
| 265 | 266 | 267 |
| 268 | 269 | 270 |
| 271 | 272 | 273 |
| 274 | 275 | 276 |
| 277 | 278 | 279 |
| 280 | 281 | 282 |
| 283 | 284 | 285 |
| 286 | 287 | 288 |
| 289 | 290 | 291 |
| 292 | 293 | 294 |
| 295 | 296 | 297 |
| 298 | 299 | 300 |
| 301 | 302 | 303 |
| 304 | 305 | 306 |
| 307 | 308 | 309 |
| 310 | 311 | 312 |
| 313 | 314 | 315 |
| 316 | 317 | 318 |
| 319 | 320 | 321 |
| 322 | 323 | 324 |
| 325 | 326 | 327 |
| 328 | 329 | 330 |
| 331 | 332 | 333 |
| 334 | 335 | 336 |
| 337 | 338 | 339 |
| 340 | 341 | 342 |
| 343 | 344 | 345 |
| 346 | 347 | 348 |
| 349 | 350 | 351 |
| 352 | 353 | 354 |
| 355 | 356 | 357 |
| 358 | 359 | 360 |
| 361 | 362 | 363 |
| 364 | 365 | 366 |
| 36 | | |

| LIMIT % | CONTENT % | LIMIT % |
|---------|-----------|---------|
| 1 | 1 | 1 |

X ----- ● ----- △

10 20 30 40 50

| STANDARD PENETRATION | BLOWS/FT | CORRECTION | | CORRECTED PENETRATION |
|-------------------------|----------|------------|-------|--------------------------|
| | | DEPTH | TEMP. | |
| 10 | 10 | 0.00 | 0.00 | 10.00 |
| 20 | 20 | 0.00 | 0.00 | 20.00 |
| 30 | 30 | 0.00 | 0.00 | 30.00 |
| 40 | 40 | 0.00 | 0.00 | 40.00 |
| 50 | 50 | 0.00 | 0.00 | 50.00 |
| 60 | 60 | 0.00 | 0.00 | 60.00 |
| 70 | 70 | 0.00 | 0.00 | 70.00 |
| 80 | 80 | 0.00 | 0.00 | 80.00 |
| 90 | 90 | 0.00 | 0.00 | 90.00 |
| 100 | 100 | 0.00 | 0.00 | 100.00 |
| 110 | 110 | 0.00 | 0.00 | 110.00 |
| 120 | 120 | 0.00 | 0.00 | 120.00 |
| 130 | 130 | 0.00 | 0.00 | 130.00 |
| 140 | 140 | 0.00 | 0.00 | 140.00 |
| 150 | 150 | 0.00 | 0.00 | 150.00 |
| 160 | 160 | 0.00 | 0.00 | 160.00 |
| 170 | 170 | 0.00 | 0.00 | 170.00 |
| 180 | 180 | 0.00 | 0.00 | 180.00 |
| 190 | 190 | 0.00 | 0.00 | 190.00 |
| 200 | 200 | 0.00 | 0.00 | 200.00 |
| 210 | 210 | 0.00 | 0.00 | 210.00 |
| 220 | 220 | 0.00 | 0.00 | 220.00 |
| 230 | 230 | 0.00 | 0.00 | 230.00 |
| 240 | 240 | 0.00 | 0.00 | 240.00 |
| 250 | 250 | 0.00 | 0.00 | 250.00 |
| 260 | 260 | 0.00 | 0.00 | 260.00 |
| 270 | 270 | 0.00 | 0.00 | 270.00 |
| 280 | 280 | 0.00 | 0.00 | 280.00 |
| 290 | 290 | 0.00 | 0.00 | 290.00 |
| 300 | 300 | 0.00 | 0.00 | 300.00 |
| 310 | 310 | 0.00 | 0.00 | 310.00 |
| 320 | 320 | 0.00 | 0.00 | 320.00 |
| 330 | 330 | 0.00 | 0.00 | 330.00 |
| 340 | 340 | 0.00 | 0.00 | 340.00 |
| 350 | 350 | 0.00 | 0.00 | 350.00 |
| 360 | 360 | 0.00 | 0.00 | 360.00 |
| 370 | 370 | 0.00 | 0.00 | 370.00 |
| 380 | 380 | 0.00 | 0.00 | 380.00 |
| 390 | 390 | 0.00 | 0.00 | 390.00 |
| 400 | 400 | 0.00 | 0.00 | 400.00 |
| 410 | 410 | 0.00 | 0.00 | 410.00 |
| 420 | 420 | 0.00 | 0.00 | 420.00 |
| 430 | 430 | 0.00 | 0.00 | 430.00 |
| 440 | 440 | 0.00 | 0.00 | 440.00 |
| 450 | 450 | 0.00 | 0.00 | 450.00 |
| 460 | 460 | 0.00 | 0.00 | 460.00 |
| 470 | 470 | 0.00 | 0.00 | 470.00 |
| 480 | 480 | 0.00 | 0.00 | 480.00 |
| 490 | 490 | 0.00 | 0.00 | 490.00 |
| 500 | 500 | 0.00 | 0.00 | 500.00 |
| 510 | 510 | 0.00 | 0.00 | 510.00 |
| 520 | 520 | 0.00 | 0.00 | 520.00 |
| 530 | 530 | 0.00 | 0.00 | 530.00 |
| 540 | 540 | 0.00 | 0.00 | 540.00 |
| 550 | 550 | 0.00 | 0.00 | 550.00 |
| 560 | 560 | 0.00 | 0.00 | 560.00 |
| 570 | 570 | 0.00 | 0.00 | 570.00 |
| 580 | 580 | 0.00 | 0.00 | 580.00 |
| 590 | 590 | 0.00 | 0.00 | 590.00 |
| 600 | 600 | 0.00 | 0.00 | 600.00 |
| 610 | 610 | 0.00 | 0.00 | 610.00 |
| 620 | 620 | 0.00 | 0.00 | 620.00 |
| 630 | 630 | 0.00 | 0.00 | 630.00 |
| 640 | 640 | 0.00 | 0.00 | 640.00 |
| 650 | 650 | 0.00 | 0.00 | 650.00 |
| 660 | 660 | 0.00 | 0.00 | 660.00 |
| 670 | 670 | 0.00 | 0.00 | 670.00 |
| 680 | 680 | 0.00 | 0.00 | 680.00 |
| 690 | 690 | 0.00 | 0.00 | 690.00 |
| 700 | 700 | 0.00 | 0.00 | 700.00 |
| 710 | 710 | 0.00 | | |

| | PENETRATION | BLOWS/FT. |
|----|-------------|-----------|
| 10 | 20 | 20 |
| 10 | 20 | 40 |
| 10 | 20 | 60 |
| 10 | 20 | 80 |
| 10 | 20 | 100 |
| 10 | 20 | 120 |
| 10 | 20 | 140 |
| 10 | 20 | 160 |
| 10 | 20 | 180 |
| 10 | 20 | 200 |
| 10 | 20 | 220 |
| 10 | 20 | 240 |
| 10 | 20 | 260 |
| 10 | 20 | 280 |
| 10 | 20 | 300 |
| 10 | 20 | 320 |
| 10 | 20 | 340 |
| 10 | 20 | 360 |
| 10 | 20 | 380 |
| 10 | 20 | 400 |
| 10 | 20 | 420 |
| 10 | 20 | 440 |
| 10 | 20 | 460 |
| 10 | 20 | 480 |
| 10 | 20 | 500 |
| 10 | 20 | 520 |
| 10 | 20 | 540 |
| 10 | 20 | 560 |
| 10 | 20 | 580 |
| 10 | 20 | 600 |
| 10 | 20 | 620 |
| 10 | 20 | 640 |
| 10 | 20 | 660 |
| 10 | 20 | 680 |
| 10 | 20 | 700 |
| 10 | 20 | 720 |
| 10 | 20 | 740 |
| 10 | 20 | 760 |
| 10 | 20 | 780 |
| 10 | 20 | 800 |
| 10 | 20 | 820 |
| 10 | 20 | 840 |
| 10 | 20 | 860 |
| 10 | 20 | 880 |
| 10 | 20 | 900 |
| 10 | 20 | 920 |
| 10 | 20 | 940 |
| 10 | 20 | 960 |
| 10 | 20 | 980 |
| 10 | 20 | 1000 |
| 10 | 20 | 1020 |
| 10 | 20 | 1040 |
| 10 | 20 | 1060 |
| 10 | 20 | 1080 |
| 10 | 20 | 1100 |
| 10 | 20 | 1120 |
| 10 | 20 | 1140 |
| 10 | 20 | 1160 |
| 10 | 20 | 1180 |
| 10 | 20 | 1200 |
| 10 | 20 | 1220 |
| 10 | 20 | 1240 |
| 10 | 20 | 1260 |
| 10 | 20 | 1280 |
| 10 | 20 | 1300 |
| 10 | 20 | 1320 |
| 10 | 20 | 1340 |
| 10 | 20 | 1360 |
| 10 | 20 | 1380 |
| 10 | 20 | 1400 |
| 10 | 20 | 1420 |
| 10 | 20 | 1440 |
| 10 | 20 | 1460 |
| 10 | 20 | 1480 |
| 10 | 20 | 1500 |
| 10 | 20 | 1520 |
| 10 | 20 | 1540 |
| 10 | 20 | 1560 |
| 10 | 20 | 1580 |
| 10 | 20 | 1600 |
| 10 | 20 | 1620 |
| 10 | 20 | 1640 |
| 10 | 20 | 1660 |
| 10 | 20 | 1680 |
| 10 | 20 | 1700 |
| 10 | 20 | 1720 |
| 10 | 20 | 1740 |
| 10 | 20 | 1760 |
| 10 | 20 | 1780 |
| 10 | 20 | 1800 |
| 10 | 20 | 1820 |
| 10 | 20 | 1840 |
| 10 | 20 | 1860 |
| 10 | 20 | 1880 |
| 10 | 20 | 1900 |
| 10 | 20 | 1920 |
| 10 | 20 | 1940 |
| 10 | 20 | 1960 |
| 10 | 20 | 1980 |
| 10 | 20 | 2000 |
| 10 | 20 | 2020 |
| 10 | 20 | 2040 |
| 10 | 20 | 2060 |
| 10 | 20 | 2080 |
| 10 | 20 | 2100 |
| 10 | 20 | 2120 |
| 10 | 20 | 2140 |
| 10 | 20 | 2160 |
| 10 | 20 | 2180 |
| 10 | 20 | 2200 |
| 10 | 20 | 2220 |
| 10 | 20 | 2240 |
| 10 | 20 | 2260 |
| 10 | 20 | 2280 |
| 10 | 20 | 2300 |
| 10 | 20 | 2320 |
| 10 | 20 | 2340 |
| 10 | 20 | 2360 |
| 10 | 20 | 2380 |
| 10 | 20 | 2400 |
| 10 | 20 | 2420 |
| 10 | 20 | 2440 |
| 10 | 20 | 2460 |
| 10 | 20 | 2480 |
| 10 | 20 | 2500 |
| 10 | 20 | 2520 |
| 10 | 20 | 2540 |
| 10 | 20 | 2560 |
| 10 | 20 | 2580 |
| 10 | 20 | 2600 |
| 10 | 20 | 2620 |
| 10 | 20 | 2640 |
| 10 | 20 | 2660 |
| 10 | 20 | 2680 |
| 10 | 20 | 2700 |
| 10 | 20 | 2720 |
| 10 | 20 | 2740 |
| 10 | 20 | 2760 |
| 10 | 20 | 2780 |
| 10 | 20 | 2800 |
| 10 | 20 | 2820 |
| 10 | 20 | |

A horizontal number line with tick marks at 10, 20, 30, 40, and 50.

| | | | | |
|--|--|---|--|--|
| | | * | | |
|--|--|---|--|--|

THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES: IN-SITU, THE TRANSITION MAY BE GRADUAL.

| WL | WS OR WD |
|----|----------|
|----|----------|

BORING STARTED

12/5/89

STS OFFICE

Northbrook-01

| WL | BCR | ACR |
|----|-----|-----|
|----|-----|-----|

BORING COMPLETED

12/5/89

DRAWN BY

KKB

| | |
|-----------|----|
| SHEET NO. | OF |
|-----------|----|

1 1

WL

RIG

FOREMAN

APP'D BY

LMB/nt

STS JOB NO.

25123-XF



STS Consultants Ltd.

OWNER

Great Lakes Naval Training Center

PROJECT NAME

Harbor Material Analysis

LOG OF BORING NUMBER

B-205

ARCHITECT-ENGINEER

SITE LOCATION

Great Lakes, Illinois

| DEPTH (FT) ELEVATION (FT) | SAMPLE NO. | SAMPLE TYPE | SAMPLE DISTANCE RECOVERY | DESCRIPTION OF MATERIAL | UNIT DRY WT. LBS./FT. ³ | UNCONFINED COMPRESSIVE STRENGTH TONS/FT. ² | | | | | PLASTIC LIMIT % | | | WATER CONTENT % | | | LIQUID LIMIT % | | |
|------------------------------|------------|-------------|-----------------------------|--|---------------------------------------|--|---|---|---|---|-----------------|---|---|-----------------|---|---|----------------|---|---|
| | | | | | | 1 | 2 | 3 | 4 | 5 | 1 | 2 | 3 | 4 | 5 | 1 | 2 | 3 | 4 |
| 0 | | | | SURFACE ELEVATION | | | | | | | | | | | | | | | |
| 2.5 | | | | Water | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | |
| 7.5 | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | |
| 12.5 | | | | | | | | | | | | | | | | | | | |
| 15 | 1 | OS | | Clayey silt - gray - saturated (ML) Note: Sample 2 slightly organic | | | | | | | | | | | | | | | |
| 17.3 | 2 | OS | | | | | | | | | | | | | | | | | |
| | | | | END OF BORING | | | | | | | | | | | | | | | |

THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES: IN-SITU, THE TRANSITION MAY BE GRADUAL.

| | | | | | |
|----|----------|--------------------|------------------|------------|---------------|
| WL | WS OR WD | BORING STARTED | 12/5/89 | STS OFFICE | Northbrook-01 |
| WL | BCR | ACR | BORING COMPLETED | DRAWN BY | SHEET NO. OF |
| | | | 12/5/89 | KKB | 1 1 |
| WL | | RIG | FOREMAN | APP'D BY | STS JOB NO. |
| | | Tripod and Cathead | Jack | LMB/nt | 25123-XF |



STS Consultants Ltd.

OWNER

Great Lakes Naval Training Center

PROJECT NAME

Harbor Material Analysis

LOG OF BORING NUMBER

B-206

ARCHITECT-ENGINEER

SITE LOCATION

Great Lakes, Illinois

| DEPTH (FT) ELEVATION (FT) | SAMPLE NO. | SAMPLE TYPE | SAMPLE DISTANCE | RECOVERY | DESCRIPTION OF MATERIAL | UNIT DRY WT. LBS./FT. ³ | UNCONFINED COMPRESSIVE STRENGTH TONS/FT. ² | PLASTIC LIMIT % | WATER CONTENT % | LIQUID LIMIT % | STANDARD PENETRATION | BLOWS/FT. |
|------------------------------|------------|-------------|-----------------|----------|--|---------------------------------------|--|--------------------|--------------------|-------------------|-------------------------|-----------|
| 2.5 | | | | | Water | | | | | | | |
| 5 | | | | | | | | | | | | |
| 7.5 | | | | | | | | | | | | |
| 10 | 1 | ST | | | Silty fine sand - brownish gray - saturated (SM) Note: Sample 2 recovered from 11.5 to 14.0' at 2' offset | | | | | | | |
| 12.5 | 2 | OS | | | | | | | | | | |
| 14 | | | | | END OF BORING | | | | | | | |

THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES: IN-SITU, THE TRANSITION MAY BE GRADUAL.

| | | | |
|----|---------------------------|---------------------------|--|
| WL | WS OR WD | BORING STARTED 12/5/89 | STS OFFICE Northbrook-01 |
| WL | BCR | ACR | BORING COMPLETED 12/5/89 |
| WL | RIG Tripod and Cathead | FOREMAN Jack | APP'D BY LMB/nt |
| | | | SHEET NO. 1 OF 1 STS JOB NO. 25123-XF |



STS Consultants Ltd.

OWNER

Great Lakes Naval Training Center

PROJECT NAME

Harbor Material Analysis

LOG OF BORING NUMBER

B-207

ARCHITECT-ENGINEER

SITE LOCATION

Great Lakes, Illinois

| DEPTH (FT) ELEVATION (FT) | SAMPLE NO. | SAMPLE TYPE | SAMPLE DISTANCE RECOVERY | DESCRIPTION OF MATERIAL | UNIT DRY WT. LBS./FT. ³ | UNCONFINED COMPRESSIVE STRENGTH TONS/FT. ² | PLASTIC LIMIT % | WATER CONTENT % | LIQUID LIMIT % | STANDARD PENETRATION | BLOWS/FT. |
|------------------------------|------------|-------------|-----------------------------|--|---------------------------------------|--|--------------------|--------------------|-------------------|-------------------------|-----------|
| × | | | | SURFACE ELEVATION | | | × | ● | △ | ⊗ | ⊗ |
| 2.5 | | | | Water | | | | | | | |
| 5 | | | | | | | | | | | |
| 7.5 | 1 | OS | | Fine sand - brownish gray - saturated (SP) | | | | | | | |
| 10 | 2 | OS | | | | | | | | | |
| 12.5 | 3 | SS | | | | | | | | | |
| | | | | END OF BORING | | | | | | | |

THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES: IN-SITU, THE TRANSITION MAY BE GRADUAL.

| | | | | | |
|----|----------|----------------|--------------------|-------------|---------------|
| WL | WS OR WD | BORING STARTED | 12/5/89 | STS OFFICE | Northbrook-01 |
| WL | BCR | ACR | BORING COMPLETED | DRAWN BY | KKB |
| | | | 12/5/89 | SHEET NO. | 1 OF 1 |
| WL | | RIG | Tripod and Cathead | APP'D BY | LMB/nt |
| | | FOREMAN | Jack | STS JOB NO. | 25123-XF |



B

[illegible]

MATERIAL ANALYSIS FOR DREDGE AND FILL ACTIVITIES
For Section 401 Water Quality Certification
From the Illinois Environmental Protection Agency

STS CONSULTANTS, LTD.

GRAIN SIZE DISTRIBUTION (ASTM D 422)

Project : GREAT LAKES TRAINING CENTER
Boring/Source: B-201
Sampl Number: S1-S3
Depth (feet): 4-9
USCS Classification: --
Soil Description : SANDY SILT-GRAY

STS Job No. : 25123-XF
Date : 12-12-89
LL: - PL: - PI: -
WC: - SP.GR.: -

SIEVE ANALYSIS --

SAMPLE WEIGHT: 25.00 GRAMS

| SIEVE SIZE | WEIGHT RETAINED | PER CENT RETAINED | PER CENT PASSING |
|---------------|--------------------|----------------------|---------------------|
| #230 | 10.29 | 41.16 | 58.84 |

MATERIAL ANALYSIS FOR DREDGE AND FILL ACTIVITIES
For Section 401 Water Quality Certification
From the Illinois Environmental Protection Agency

STS CONSULTANTS, LTD.

GRAIN SIZE DISTRIBUTION (ASTM D 422)

| | | | |
|---------------------|--|-------------|-------------|
| Project | : GREAT LAKES TRAINING CENTER | STS Job No. | : 25123-XF |
| Boring/Source | : B-202 | Date | : 12-12-89 |
| Sample Number | : S1, S2 | LL: - | PL: - PI: - |
| Depth (feet) | : 0-5 | WC: - | SP.GR.: - |
| USCS Classification | : -- | | |
| Soil Description | : F-C SAND AND SLAG, TRACE SILT SIZES-GRAY | | |

SIEVE ANALYSIS --

SAMPLE WEIGHT: 25.00 GRAMS

| SIEVE SIZE | WEIGHT RETAINED | PER CENT RETAINED | PER CENT PASSING |
|---------------|--------------------|----------------------|---------------------|
| #230 | 23.62 | 94.48 | 5.52 |

MATERIAL ANALYSIS FOR DREDGE AND FILL ACTIVITIES
For Section 401 Water Quality Certification
From the Illinois Environmental Protection Agency

STS CONSULTANTS, LTD.

GRAIN SIZE DISTRIBUTION (ASTM D 422)

| | | | |
|----------------------|------------------------------------|-------------|-------------|
| Project | : GREAT LAKES TRAINING CENTER | STS Job No. | : 25123-XF |
| Boring/Source: | B-203 | Date | : 12-12-89 |
| Sample Number: | S1, S2 | LL: - | PL: - PI: - |
| Depth (feet): | 0-5 | WC: - | SP.GR.: - |
| USCS Classification: | -- | | |
| Soil Description | : F-C SAND, LITTLE SILT SIZES-GRAY | | |

SIEVE ANALYSIS --

SAMPLE WEIGHT: 25.11 GRAMS

| SIEVE SIZE | WEIGHT RETAINED | PER CENT RETAINED | PER CENT PASSING |
|---------------|--------------------|----------------------|---------------------|
| #230 | 20.95 | 83.43 | 16.57 |

MATERIAL ANALYSIS FOR DREDGE AND FILL ACTIVITIES
For Section 401 Water Quality Certification
From the Illinois Environmental Protection Agency

STS CONSULTANTS, LTD.

GRAIN SIZE DISTRIBUTION (ASTM D 422)

Project : GREAT LAKES TRAINING CENTER
Boring/Source: B-204
Sample Number: S1-S3
Depth (feet): 3.3-8.3
USCS Classification: --
Soil Description : SANDY SILT-GRAY

STS Job No. : 25123-XF
Date : 12-12-89
LL: - PL: - PI: -
WC: - SP.GR.: -

SIEVE ANALYSIS --

SAMPLE WEIGHT: 25.10 GRAMS

| SIEVE SIZE | WEIGHT RETAINED | PER CENT RETAINED | PER CENT PASSING |
|---------------|--------------------|----------------------|---------------------|
| #230 | 6.80 | 27.09 | 72.91 |

MATERIAL ANALYSIS FOR DREDGE AND FILL ACTIVITIES
For Section 401 Water Quality Certification
From the Illinois Environmental Protection Agency

STS CONSULTANTS, LTD.

GRAIN SIZE DISTRIBUTION (ASTM D 422)

Project : GREAT LAKES TRAINING CENTER
Boring/Source: B-205
Sampl Number: S1,S2
Depth (feet): 12.3-17.3
USCS Classification: --
Soil Description : SILT,TRACE F SAND-GRAY

STS Job No. : 25123-XF
Date : 12-12-89
LL: - PL: - PI: -
WC: - SP.GR.: -

SIEVE ANALYSIS --

SAMPLE WEIGHT: 25.06 GRAMS

| SIEVE SIZE | WEIGHT RETAINED | PER CENT RETAINED | PER CENT PASSING |
|---------------|--------------------|----------------------|---------------------|
| #230 | 1.26 | 5.03 | 94.97 |

MATERIAL ANALYSIS FOR DREDGE AND FILL ACTIVITIES
For Section 401 Water Quality Certification
From the Illinois Environmental Protection Agency

STS CONSULTANTS, LTD.

GRAIN SIZE DISTRIBUTION (ASTM D 422)

Project : GREAT LAKES TRAINING CENTER
Boring/Source: B-206
Sample Number: S1, S2
Depth (feet): 7.8-12.8
USCS Classification: --
Soil Description : F SANDY SILT-GRAY

STS Job No. : 25123-XF
Date : 12-12-89
LL: - PL: - PI: -
WC: - SP.GR.: -

SIEVE ANALYSIS --

SAMPLE WEIGHT: 25.26 GRAMS

| SIEVE SIZE | WEIGHT RETAINED | PER CENT RETAINED | PER CENT PASSING |
|---------------|--------------------|----------------------|---------------------|
| #230 | 11.32 | 44.81 | 55.19 |

MATERIAL ANALYSIS FOR DREDGE AND FILL ACTIVITIES
For Section 401 Water Quality Certification
From the Illinois Environmental Protection Agency

STS CONSULTANTS, LTD.

GRAIN SIZE DISTRIBUTION (ASTM D 422)

Project : GREAT LAKES TRAINING CENTER
Boring/Source: B-207
Sample Number: S1-S3
Depth (feet): 6.9-11.9
USCS Classification: --
Soil Description : F SAND, LITTLE SILT-GRAY

STS Job No. : 25123-XF
Date : 12-12-89
LL: - PL: - PI: -
WC: - SP.GR.: -

SIEVE ANALYSIS --

SAMPLE WEIGHT: 25.22 GRAMS

| SIEVE SIZE | WEIGHT RETAINED | PER CENT RETAINED | PER CENT PASSING |
|---------------|--------------------|----------------------|---------------------|
| #230 | 20.87 | 82.75 | 17.25 |



O

Radian Work Order 89-12-058

Analytical Report
12/28/89

STS CONSULTANTS LTD

STS CONSULTANTS LTD
RADIAN - MILWAUKEE
5103 W. BELOIT ROAD
MILWAUKEE, WI. 53214
C. APPLGATE, cc J.WOJTKIEWICZ

Customer Work Identification Elutriate and Sediment
Purchase Order Number 393-001-13-01

Contents:

- 1 Analytical Data Summary
- 2 Sample History
- 3 Comments Summary
- 4 Notes and Definitions

Radian Analytical Services
8501 Mo-Pac Boulevard
P. O. Box 201088
Austin, TX 78720-1088

512/454-4797

Client Services Coordinator: LABENDELE

Certified by:

Marilyn Melton

Previously Reported on 12/22/89.

STS CONSULTANTS LTD

Radian Work Order: 89-12-058

Method:SW8080-Pesticides/PCBs (1)

List:8080PC/PE MATRIX SPIKE

Sample ID: B-207 MS B-207 MSD

Factor: 199 196

Results in: % %

08B 09B

Matrix: solid solid

| | | |
|------------|--------|--------|
| Aldrin | 118 D | 116 D |
| gamma-BHC | 82 D | 79 D |
| 4,4'-DDT | 108 | 103 |
| Dieldrin | 89 | 84 |
| Endrin | 96 | 92 |
| Heptachlor | 208 DQ | 139 DQ |

Surrogate Recovery(%)

Dibutylchloroendate 105 108

Control Limits: 20 to 150

2,4,5,6-Tetrachloro-m-xylene 201DQ 218DQ

Control Limits: 17 to 152

D Sample diluted for this analyte

Q Outside control limits

(1) For a detailed description of flags and technical terms in this report refer to Appendix A in this report.

STS CONSULTANTS LTD
 Radian Work Order: 89-12-058

Method: SW8080-Pesticides/PCBs (1)

List: 8080 LIST FOR PCB'S-SOLIDS

| Sample ID: | B-201 | B-202 | B-203 | B-204 | B-205 | B-206 |
|-------------|-------|-------|-------|-------|-------|-------|
| Factor: | 500 | 495 | 497 | 1000 | 488 | 976 |
| Results in: | ug/Kg | ug/Kg | ug/Kg | ug/Kg | ug/Kg | ug/Kg |
| | 01B | 02B | 03B | 04B | 05B | 06B |
| Matrix: | solid | solid | solid | solid | solid | solid |

| | | | | | | |
|----------|------|-----|-----|------|-----|------|
| PCB-1016 | <50 | <50 | <50 | <100 | <49 | <98 |
| PCB-1221 | <100 | <99 | <99 | <200 | <98 | <200 |
| PCB-1232 | <100 | <99 | <99 | <200 | <98 | <200 |
| PCB-1242 | <50 | <50 | <50 | <100 | <49 | <98 |
| PCB-1248 | <50 | <50 | <50 | <100 | <49 | <98 |
| PCB-1254 | <100 | <99 | <99 | 2400 | <98 | <200 |
| PCB-1260 | <100 | <99 | <99 | <200 | <98 | <200 |

Surrogate Recovery(%)

| | | | | | | |
|------------------------------|-------|-------|-------|-------|-------|-------|
| Dibutylchloroendate | 545 Q | 98 | 538 Q | 288 Q | 113 | 1100 |
| Control Limits: 20 to 150 | | | | | | |
| 2,4,5,6-Tetrachloro-m-xylene | 224 Q | 3100Q | 186 Q | 234 Q | 6400Q | 417 Q |
| Control Limits: 17 to 152 | | | | | | |

Q Outside control limits

D Sample diluted for this analyte

(1) For a detailed description of flags and technical terms in this report refer to Appendix A in this report.

STS CONSULTANTS LTD
 Radian Work Order: 89-12-058

Method: SW8080-Pesticides/PCBs (1)

List: 8080 LIST FOR PCB'S-SOLIDS

Sample ID: B-207 REAGENT BLANK

Factor: 497 100

Results in: ug/Kg ug/Kg

07B 12A

Matrix: solid solid

| | | |
|----------|-----|-----|
| PCB-1016 | <50 | <10 |
| PCB-1221 | <99 | <20 |
| PCB-1232 | <99 | <20 |
| PCB-1242 | <50 | <10 |
| PCB-1248 | <50 | <10 |
| PCB-1254 | <99 | <20 |
| PCB-1260 | <99 | <20 |

Surrogate Recovery(%)

Dibutylchloroendate 95 112

Control Limits: 20 to 150

2,4,5,6-Tetrachloro-m-xylene 203 Q 95

Control Limits: 17 to 152

Q Outside control limits

(1) For a detailed description of flags and technical terms in this report refer to Appendix A in this report.

STS CONSULTANTS LTD
Radian Work Order: 89-12-058

Method:SW8310-PAH's by HPLC (1)

List:8310 Method analytes

| Sample ID: | B-201 | B-202 | B-203 | B-204 | B-205 | B-206 |
|-------------|-------|-------|-------|-------|-------|-------|
| Factor: | 500 | 500 | 500 | 2500 | 490 | 2500 |
| Results in: | ug/Kg | ug/Kg | ug/Kg | ug/Kg | ug/Kg | ug/Kg |
| | 01A | 02A | 03A | 04A | 05A | 06A |
| Matrix: | solid | solid | solid | solid | solid | solid |

| | | | | | | |
|--------------------------|-------|-------|-------|---------|-------|--------|
| Acenaphthalene | <1200 | <1200 | <1200 | <5800 | <1200 | <5800 |
| Acenaphthene | <900 | <900 | <900 | <4500 | <900 | <4500 |
| Anthracene | <330 | <330 | <330 | <1700 | <330 | <1700 |
| Benzo(a)anthracene | 560 | 270 | 500 | 1100 | 180 | 740 |
| Benzo(a)pyrene | 310 D | 92 *D | 360 | 810 | 190 | 1300 |
| Benzo(b)fluoranthene | 570 | 260 | 540 | 740 | 200 | 260 |
| Benzo(g,h,i)perylene | 250 | 160 * | 310 | 680 * | 150 * | 370 * |
| Benzo(k)fluoranthene | NR | NR | NR | NR | NR | NR |
| Chrysene | 620 | 360 | 670 | 1800 | 310 | 770 |
| Dibenzo(a,h)anthracene | 98 | 55 * | 110 | 260 * | 47 * | 170 * |
| Fluoranthene | 170 * | <110 | 170 * | 450 *D | <110 | <530 |
| Fluorene | 120 * | <110 | <110 | 266 *D | <110 | <530 |
| Indeno(1,2,3-cd)pyrene | 780 | 630 | 190 | 704 D | 720 | 250 D |
| Naphthalene | NR | NR | NR | NR | NR | NR |
| Phenanthrene | 850 * | 410 * | 770 * | 2100 *D | <320 | 650 *D |
| Pyrene | 830 | 450 * | 970 | 2100 * | 340 * | 910 * |
| Surrogate Recovery(%) | | | | | | |
| Terphenyl-d14 | 68 | 78 | 58 | NC | 28 | 119 D |
| Control Limits: 0 to 180 | | | | | | |

D Sample diluted for this analyte

NR Analyte not requested

* Est. result less than 5 times detection limit

NC Not calculated

(1) For a detailed description of flags and technical terms in this report refer to Appendix A in this report.

STS CONSULTANTS LTD

Radian Work Order: 89-12-058

Method:SW8310-PAH's by HPLC (1)

List:8310 Method analytes

Sample ID: B-207 REAGENT BLANK

Factor: 490 100

Results in: ug/Kg ug/Kg

07A 11A

Matrix: solid solid

| | | |
|------------------------|--------------|------|
| Acenaphthalene | <1100 | <230 |
| Acenaphthene | <880 | <180 |
| Anthracene | <320 | <66 |
| Benzo(a)anthracene | <u>550</u> | <1.3 |
| Benzo(a)pyrene | <u>360</u> | <2.3 |
| Benzo(b)fluoranthene | <u>620</u> | <1.8 |
| Benzo(g,h,i)perylene | <u>320</u> | <7.6 |
| Benzo(k)fluoranthene | NR | NR |
| Chrysene | <u>580</u> | <1.3 |
| Dibenzo(a,h)anthracene | <u>110</u> | <3.0 |
| Fluoranthene | <u>130 *</u> | <21 |
| Fluorene | <100 | <21 |
| Indeno(1,2,3-cd)pyrene | <u>800</u> | <4.3 |
| Naphthalene | NR | NR |
| Phenanthrene | <u>600 *</u> | <64 |
| Pyrene | <u>630 *</u> | <27 |

Surrogate Recovery(%)

Terphenyl-d14 80 63

Control Limits: 0 to 180

NR Analyte not requested

* Est. result less than 5 times detection limit

(1) For a detailed description of flags and technical terms in this report refer to Appendix A in this report.

STS CONSULTANTS LTD
 Radian Work Order: 89-12-058

Method: SW8310-PAH's by HPLC (1)

List: Matrix Spike Analyte List

| Sample ID: | B-207 MS | B-207 MSD | RECOVERY CHECK |
|-------------|----------|-----------|----------------|
| Factor: | 1 | 1 | 1 |
| Results in: | % | % | % |
| | 08A | 09A | 10A |
| Matrix: | solid | solid | solid |

| | B-207 MS | B-207 MSD | RECOVERY CHECK |
|------------------------|----------|-----------|----------------|
| Acenaphthalene | 48 | 41 | 78 |
| Acenaphthene | 44 | 45 | 76 |
| Anthracene | 53 | 48 | 84 |
| Benzo(k)fluoranthene | 52 | 35 | 92 |
| Dibenzo(a,h)anthracene | 40 | 25 | 87 |
| Fluorene | 35 | 28 | 81 |
| Naphthalene | 10 | 4 | 76 |
| Phenanthrene | 56 | 50 | 82 |

Surrogate Recovery(%)

| | | | |
|---------------|----|----|----|
| Terphenyl-d14 | 69 | NC | 83 |
|---------------|----|----|----|

Control Limits: 0 to 180

NC Not calculated

(1) For a detailed description of flags and technical terms in this report refer to Appendix A in this report.

STS CONSULTANTS LTD
 Radian Work Order: 89-12-058

| Sample Identifications and Dates | | | | | | |
|----------------------------------|----------|----------|----------|----------|----------|----------|
| Sample ID | B-201 | B-202 | B-203 | B-204 | B-205 | B-206 |
| Date Sampled | 12/06/89 | 12/06/89 | 12/06/89 | 12/05/89 | 12/05/89 | 12/05/89 |
| Date Received | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 |
| Matrix | solid | solid | solid | solid | solid | solid |
| | 01 | 02 | 03 | 04 | 05 | 06 |
| SW8080-Pesticides/PCBs | | | | | | |
| Prepared | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 |
| Analyzed | 12/12/89 | 12/12/89 | 12/12/89 | 12/13/89 | 12/13/89 | 12/12/89 |
| Analyst | REM | REM | REM | REM | REM | REM |
| File ID | HP422 | HP411 | HP412 | HP425 | HP426 | HP415 |
| Blank ID | HP44 | HP44 | HP44 | HP44 | HP44 | HP44 |
| Instrument | HP4 | HP4 | HP4 | HP4 | HP4 | HP4 |
| Report as | received | received | received | received | received | received |
| SW8310-PAH's by HPLC | | | | | | |
| Prepared | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 |
| Analyzed | 12/20/89 | 12/20/89 | 12/20/89 | 12/20/89 | 12/20/89 | 12/20/89 |
| Analyst | TLS | TLS | TLS | TLS | TLS | TLS |
| File ID | 311 | 314 | 315 | 338 | 317 | 339 |
| Blank ID | 322 | 322 | 322 | 322 | 322 | 322 |
| Instrument | HPLC 2 | HPLC 2 | HPLC 2 | HPLC 2 | HPLC 2 | HPLC 2 |
| Report as | received | received | received | received | received | received |

STS CONSULTANTS LTD.
 Radian Work Order: 89-12-058

| Sample Identifications and Dates | | | | | | |
|----------------------------------|----------|----------|-----------|----------------|---------------|---------------|
| Sample ID | B-207 | B-207 MS | B-207 MSD | RECOVERY CHECK | REAGENT BLANK | REAGENT BLANK |
| Date Sampled | 12/05/89 | | | | | |
| Date Received | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 |
| Matrix | solid | solid | solid | solid | solid | solid |
| | 07 | 08 | 09 | 10 | 11 | 12 |
| SW8080-Pesticides/PCBs | | | | | | |
| Prepared | | 12/08/89 | 12/08/89 | | | |
| Analyzed | | 12/12/89 | 12/12/89 | | | |
| Analyst | | REM | REM | | | |
| File ID | | HP46 | HP47 | | | |
| Blank ID | | HP44 | HP44 | | | |
| Instrument | | HP4 | HP4 | | | |
| Report as | | received | received | | | |
| SW8080-Pesticides/PCBs | | | | | | |
| Prepared | 12/08/89 | | | | | 12/08/89 |
| Analyzed | 12/12/89 | | | | | 12/12/89 |
| Analyst | REM | | | | | REM |
| File ID | HP421 | | | | | HP44 |
| Blank ID | HP44 | | | | | HP44 |
| Instrument | HP4 | | | | | HP4 |
| Report as | received | | | | | received |
| SW8310-PAH's by HPLC | | | | | | |
| Prepared | 12/08/89 | | | | 12/08/89 | |
| Analyzed | 12/20/89 | | | | 12/21/89 | |
| Analyst | TLS | | | | TLS | |
| File ID | 319 | | | | 322 | |
| Blank ID | 322 | | | | 322 | |
| Instrument | HPLC 2 | | | | HPLC 2 | |
| Report as | received | | | | received | |
| SW8310-PAH's by HPLC | | | | | | |
| Prepared | | 12/08/89 | 12/08/89 | 12/08/89 | | |
| Analyzed | | 12/20/89 | 12/20/89 | 12/20/89 | | |
| Analyst | | TLS | TLS | TLS | | |
| File ID | | 312 | 313 | 323 | | |
| Blank ID | | 322 | 322 | 322 | | |
| Instrument | | HPLC 2 | HPLC 2 | HPLC 2 | | |
| Report as | | received | received | received | | |

Appendix A

Comments, Notes and Definitions

STS CONSULTANTS LTD

Radian Work Order: 89-12-058

General Comments

8080-Unable to identify low-level PCBs due to matrix interference

Surrogates display high % recoveries due to matrix interference

STS CONSULTANTS LTD
Radian Work Order: 89-12-058

- A This flag indicates that a spike is an analytical and/or post-digestion spike. These spikes have not been subjected to the extraction or digestion step.
- B This flag indicates that the analyte was detected in the reagent blank but the sample results are not corrected for the amount in the blank.
- C Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The C flag indicates that the analyte has been confirmed by analysis on a second column.
- D This flag identifies all analytes identified in analysis at a secondary dilution factor. In an analysis some compounds can exceed the calibration range of the instrument. Therefore two analyses are performed, one at the concentration of the majority of the analytes, and a second with the sample diluted so that high concentration analyte(s) fall within the calibration range.
- E The reported value is estimated because of the presence of interference. The potential source of the interference is included in the report narrative.
- G This flag identifies a GC/MS result whose concentration exceeds the calibration range for that specific analysis. Usually if one or more compounds have a response greater than full scale, the sample or extract is diluted and re-analyzed.
- I This is a general purpose flag for those situations not covered by the standard flags. The specific definition of this flag is described in the Comments Summary or supplemental case narrative with the report.
- J Indicates an estimated value for GC/MS data. This flag is used either when estimating a concentration for tentatively identified compounds where a response factor of 1 is assumed, or when the mass spectral data indicate the presence of a compound that meets the identification criteria but the result is less than the sample quantitation limit.
- NA This analyte was not analyzed.
- NC Applies to RPD and spike recovery results. The relative percent difference (RPD) and spike recovery are not calculated when a result value is less than five times the detection limit or obvious matrix interferences are present. See * definition for further explanation of the unreliability of data near the detection limit. A spike recovery is not calculated when the sample result is greater than four times the spike added concentration because the spike added concentration is considered insignificant.

STS CONSULTANTS LTD

Radian Work Order: 89-12-058

- ND This flag (or <) is used to denote analytes which are not detected at or above the specified detection limit. The value to the right of the < symbol is the method specified detection limit for the sample.
- NR This analyte was not requested by the client.
- NS This analyte or surrogate was not added (spiked) to the sample for this analysis.
- N/A A result or value is not available for this parameter, usually a detection limit.
- P Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The P flag indicates that the analyte has been confirmed previously. This flag is applicable to analyses of samples arising from a regular sampling program as a specific sample source; for example, a quarterly well monitoring program.
- Q This quality control standard is outside method or laboratory specified control limits. This flag is applied to matrix spike, analytical QC spike, and surrogate recoveries; and to RPD(relative percent difference) values for duplicate analyses and matrix spike/matrix spike duplicate result.
- R This flag indicates that the analyte was detected in the reagent blank and the sample results are corrected for the amount in the blank.
- S This flag indicates that a specific result from a metals analysis has been obtained using the Method of Standard Addition.
- U Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The U flag indicates that second column was not requested.
- X Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The X flag indicates a second column confirmation was performed but the analyte was not confirmed and is likely a false positive.
- * The asterisk(*) is used to flag results which are less than five times the method specified detection limit. Studies have shown that the uncertainty of the analysis will increase exponentially as the method detection limit is approached. These results should be considered approximate.

STS CONSULTANTS LTD
Radian Work Order: 89-12-058

TERMS USED IN THIS REPORT:

Analyte - A chemical for which a sample is to be analyzed. The analysis will meet EPA method and QC specifications.

Compound - See Analyte.

Detection Limit - The method specified detection limit, which is the lower limit of quantitation specified by EPA for a method. Radian staff regularly assess their laboratories' method detection limits to verify that they meet or are lower than those specified by EPA. Detection limits which are higher than method limits are based on experimental values at the 99% confidence level. Note, the detection limit may vary from that specified by EPA based on sample size, dilution or cleanup.
(Refer to Factor, below)

EPA Method - The EPA specified method used to perform an analysis. EPA has specified standard methods for analysis of environmental samples. Radian will perform its analyses and accompanying QC tests in conformance with EPA methods unless otherwise specified.

Factor - Default method detection limits are based on analysis of clean water samples. A factor is required to calculate sample specific detection limits based on alternate matrices (soil or water), use of cleanup procedures, or dilution of extracts/digestates. For example, extraction or digestion of 10 grams of soil in contrast to 1 liter of water will result in a factor of 100.

Matrix - The sample material. Generally, it will be soil, water, air, oil, or solid waste.

Radian Work Order - The unique Radian identification code assigned to the samples reported in the analytical summary.

| | |
|--------------|---|
| Units - ug/L | micrograms per liter (parts per billion); liquids/water |
| ug/Kg | micrograms per kilogram (parts per billion); soils/solids |
| ug/M3 | micrograms per cubic meter; air samples |
| mg/L | milligrams per liter (parts per million); liquids/water |
| mg/Kg | milligrams per kilogram (parts per million); soils/solids |
| % | percent; usually used for percent recovery of QC standards |
| uS/cm | conductance unit; microSiemens/centimeter |
| mL/hr | milliliters per hour; rate of settlement of matter in water |
| NTU | turbidity unit; nephelometric turbidity unit |
| CU | color unit; equal to 1 mg/L of chloroplatinate salt |

Radian Work Order 89-12-162

Analytical Report
12/28/89

STS CONSULTANTS LTD

STS CONSULTANTS LTD
RADIAN - MILWAUKEE
5103 W. BELOIT ROAD
MILWAUKEE, WI. 53214
C. APPLEGATE, cc J. WOJTKIEWICZ

Customer Work Identification Elutriate and Sediment
Purchase Order Number 393-001-13-01

Contents:

- 1 Analytical Data Summary
- 2 Sample History
- 3 Comments Summary
- 4 Notes and Definitions

Radian Analytical Services
8501 Mo-Pac Boulevard
P. O. Box 201088
Austin, TX 78720-1088

512/454-4797

Client Services Coordinator: LABENDELE

Certified by: 

STS CONSULTANTS LTD
Radian Work Order: 89-12-162

| Method/Analyte | Sample Identifications | | | | |
|------------------|------------------------|--------|--------|--------|--------|
| | B-201 | B-202 | B-203 | B-204 | B-205 |
| | 01 | 02 | 03 | 04 | 05 |
| Matrix | soil | soil | soil | soil | soil |
| Percent moisture | | | | | |
| Percent moisture | 18.6 % | 19.1 % | 20.4 % | 37.0 % | 40.5 % |

For a detailed description of flags and technical terms in this report refer to the glossary.

STS CONSULTANTS LTD
Radian Work Order: 89-12-162

| Method/Analyte | Sample Identifications | |
|----------------|------------------------|------------|
| | B-206 | B-207 |
| Matrix | 06 soil | 07 soil |

| | | | | | |
|------------------|------|---|------|---|--|
| Percent moisture | | | | | |
| Percent moisture | 26.1 | % | 18.0 | % | |

For a detailed description of flags and technical terms in this report refer to the glossary.

STS CONSULTANTS LTD
 Radian Work Order: 89-12-162

| Sample Identifications and Dates | | | | | | |
|----------------------------------|----------|----------|----------|----------|----------|----------|
| Sample ID | B-201 | B-202 | B-203 | B-204 | B-205 | B-206 |
| Date Sampled | 12/06/89 | 12/06/89 | 12/06/89 | 12/05/89 | 12/05/89 | 12/05/89 |
| Date Received | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 | 12/08/89 |
| Matrix | soil | soil | soil | soil | soil | soil |
| | 01 | 02 | 03 | 04 | 05 | 06 |
| Percent moisture | | | | | | |
| Prepared | 12/21/89 | 12/21/89 | 12/21/89 | 12/21/89 | 12/21/89 | 12/21/89 |
| Analyzed | 12/21/89 | 12/21/89 | 12/21/89 | 12/21/89 | 12/21/89 | 12/21/89 |
| Analyst | ET | ET | ET | ET | ET | ET |
| File ID | | | | | | |
| Blank ID | | | | | | |
| Instrument | | | | | | |
| Report as | received | received | received | received | received | received |

STS CONSULTANTS LTD
Radian Work Order: 89-12-162

Sample Identifications and Dates

Sample ID B-207

Date Sampled 12/05/89
Date Received 12/08/89
Matrix soil
 07

Percent moisture

Prepared 12/21/89
Analyzed 12/21/89
Analyst ET
File ID
Blank ID
Instrument
Report as received

Appendix A

Comments, Notes and Definitions

STS CONSULTANTS LTD
Radian Work Order: 89-12-162

- A This flag indicates that a spike is an analytical and/or post-digestion spike. These spikes have not been subjected to the extraction or digestion step.
- B This flag indicates that the analyte was detected in the reagent blank but the sample results are not corrected for the amount in the blank.
- C Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The C flag indicates that the analyte has been confirmed by analysis on a second column.
- D This flag identifies all analytes identified in analysis at a secondary dilution factor. In an analysis some compounds can exceed the calibration range of the instrument. Therefore two analyses are performed, one at the concentration of the majority of the analytes, and a second with the sample diluted so that high concentration analyte(s) fall within the calibration range.
- E The reported value is estimated because of the presence of interference. The potential source of the interference is included in the report narrative.
- G This flag identifies a GC/MS result whose concentration exceeds the calibration range for that specific analysis. Usually if one or more compounds have a response greater than full scale, the sample or extract is diluted and re-analyzed.
- I This is a general purpose flag for those situations not covered by the standard flags. The specific definition of this flag is described in the Comments Summary or supplemental case narrative with the report.
- J Indicates an estimated value for GC/MS data. This flag is used either when estimating a concentration for tentatively identified compounds where a response factor of 1 is assumed, or when the mass spectral data indicate the presence of a compound that meets the identification criteria but the result is less than the sample quantitation limit.
- NA This analyte was not analyzed.
- NC Applies to RPD and spike recovery results. The relative percent difference (RPD) and spike recovery are not calculated when a result value is less than five times the detection limit or obvious matrix interferences are present. See * definition for further explanation of the unreliability of data near the detection limit. A spike recovery is not calculated when the sample result is greater than four times the spike added concentration because the spike added concentration is considered insignificant.

STS CONSULTANTS LTD

Radian Work Order: 89-12-162

- ND This flag (or <) is used to denote analytes which are not detected at or above the specified detection limit. The value to the right of the < symbol is the method specified detection limit for the sample.
- NR This analyte was not requested by the client.
- NS This analyte or surrogate was not added (spiked) to the sample for this analysis.
- N/A A result or value is not available for this parameter, usually a detection limit.
- P Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The P flag indicates that the analyte has been confirmed previously. This flag is applicable to analyses of samples arising from a regular sampling program as a specific sample source; for example, a quarterly well monitoring program.
- Q This quality control standard is outside method or laboratory specified control limits. This flag is applied to matrix spike, analytical QC spike, and surrogate recoveries; and to RPD(relative percent difference) values for duplicate analyses and matrix spike/matrix spike duplicate result.
- R This flag indicates that the analyte was detected in the reagent blank and the sample results are corrected for the amount in the blank.
- S This flag indicates that a specific result from a metals analysis has been obtained using the Method of Standard Addition.
- U Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The U flag indicates that second column was not requested.
- X Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The X flag indicates a second column confirmation was performed but the analyte was not confirmed and is likely a false positive.
- * The asterisk(*) is used to flag results which are less than five times the method specified detection limit. Studies have shown that the uncertainty of the analysis will increase exponentially as the method detection limit is approached. These results should be considered approximate.

STS CONSULTANTS LTD
Radian Work Order: 89-12-162

TERMS USED IN THIS REPORT:

Analyte - A chemical for which a sample is to be analyzed. The analysis will meet EPA method and QC specifications.

Compound - See Analyte.

Detection Limit - The method specified detection limit, which is the lower limit of quantitation specified by EPA for a method. Radian staff regularly assess their laboratories' method detection limits to verify that they meet or are lower than those specified by EPA. Detection limits which are higher than method limits are based on experimental values at the 99% confidence level. Note, the detection limit may vary from that specified by EPA based on sample size, dilution or cleanup.
(Refer to Factor, below)

EPA Method - The EPA specified method used to perform an analysis. EPA has specified standard methods for analysis of environmental samples. Radian will perform its analyses and accompanying QC tests in conformance with EPA methods unless otherwise specified.

Factor - Default method detection limits are based on analysis of clean water samples. A factor is required to calculate sample specific detection limits based on alternate matrices (soil or water), use of cleanup procedures, or dilution of extracts/digestates. For example, extraction or digestion of 10 grams of soil in contrast to 1 liter of water will result in a factor of 100.

Matrix - The sample material. Generally, it will be soil, water, air, oil, or solid waste.

Radian Work Order - The unique Radian identification code assigned to the samples reported in the analytical summary.

| | |
|--------------|---|
| Units - ug/L | micrograms per liter (parts per billion); liquids/water |
| ug/Kg | micrograms per kilogram (parts per billion); soils/solids |
| ug/M3 | micrograms per cubic meter; air samples |
| mg/L | milligrams per liter (parts per million); liquids/water |
| mg/Kg | milligrams per kilogram (parts per million); soils/solids |
| % | percent; usually used for percent recovery of QC standards |
| uS/cm | conductance unit; microSiemens/centimeter |
| mL/hr | milliliters per hour; rate of settlement of matter in water |
| NTU | turbidity unit; nephelometric turbidity unit |
| CU | color unit; equal to 1 mg/L of chloroplatinate salt |

Page 1

Received: 12/07/89

RADIAN CORP.

12/28/89 10:25:17

REPORT

Work Order # M9-12-017

REPORT STS CONSULTANTS, LTD
TO 111 PFINGSTON ROAD
NORTHBROOK, ILLINOIS 60062
ATTEN MR. PAUL BLINDAUER

PREPARED Radian Corporation
BY Milwaukee Office
5103 West Beloit Road
Milwaukee, WI 53214
ATTEN Charles S. Applegate
PHONE (414)643-2768

James R. [Signature]
CERTIFIED BY
CONTACT C APPLEGATE

CLIENT STS NORTHBRK SAMPLES 12
COMPANY STS CONSULTANTS, LTD
FACILITY 111 PFINGSTON ROAD
NORTHBROOK, ILLINOIS 60062

State of Wisconsin - Certified Laboratory
No. 241293910

WORK ID ELUTRIATE & SEDIMENT
TAKEN T. MULVEY-RADIAN COC M1491
TRANS
TYPE SLURRY
P.O. # 25123XE
INVOICE under separate cover

REFER TO END OF REPORT FOR EXPLANATION OF PROBLEM AREAS AND
ASSOCIATED FLAGS.

SAMPLE IDENTIFICATION

01 B-201 TIME 0 SLURRY
02 B-201 TIME 15 SLURRY
03 B-201 SEDIMENT
04 B-202 TIME 0
05 B-202 TIME 15 SLURRY
06 B-202 SEDIMENT
07 B-203 TIME 0 SLURRY
08 B-203 TIME 15 SLURRY
09 B-203 SEDIMENT
10 B-204 TIME 0 SLURRY
11 B-204 TIME 15 SLURRY
12 B-204 SEDIMENT

TEST CODES and NAMES used on this report

AG SILVER
AS HY ARSENIC BY HYDRIDE GEN.
BE BERYLLIUM
CD CADMIUM
CN TOTAL CYANIDE
CR CHROMIUM
CR HEX CHROMIUM-HEXAVALENT
CU COPPER
HG MERCURY
NI NICKEL
PB LEAD
SB ANTIMONY
SE HY SELENIUM BY HYDRIDE GEN.
TL THALLIUM
TOC S TOTAL ORGANIC CARBON SOIL
ZN ZINC

RECEIVED

DEC 29 1989

STS CONSULTANTS LTD.
NORTHBROOK ILLINOIS 60062

Received: 12/07/89

RADIAN CORP.

REPORT

Work Order # M9-12-017

Results by Sample

| | | | | | | | | | | | |
|--------------------------------------|------------------|-------|---------------|---|----------------|----|--------------|----|------------|----|----------------|
| SAMPLE ID <u>B-201 TIME 0 SLURRY</u> | | | | SAMPLE # <u>01</u> FRACTIONS: <u>A,B,C,D</u> | | | | | | | |
| | | | | Date & Time Collected <u>12/08/89 12:00:00</u> Category _____ | | | | | | | |
| AG | <u>0.304 E</u> | AS_HY | <u>1098 S</u> | BE | <u>0.05</u> | CD | <u>0.123</u> | CN | <u>N/A</u> | CR | <u>1.35</u> |
| | mg/L | | ug/L | | mg/L | | mg/L | | ug/L | | mg/L |
| CR_HEX | <u><0.001</u> | CU | <u>3.91</u> | HG | <u><0.4</u> | NI | <u>2.49</u> | PB | <u>5.7</u> | SB | <u><1 S</u> |
| | mg/L | | mg/L | | ug/L | | mg/L | | mg/L | | ug/L |
| SE_HY | <u>18.0</u> | TL | <u>1.80</u> | ZN | <u>9.92</u> | | | | | | |
| | ug/L | | mg/L | | mg/L | | | | | | |

| | | | | | | | | | | | |
|---------------------------------------|------------------|-------|---------------|---|-------------|----|--------------|----|---------------|----|----------------|
| SAMPLE ID <u>B-201 TIME 15 SLURRY</u> | | | | SAMPLE # <u>02</u> FRACTIONS: <u>A,B,C,D</u> | | | | | | | |
| | | | | Date & Time Collected <u>12/08/89 12:00:00</u> Category _____ | | | | | | | |
| AG | <u>0.248 E</u> | AS_HY | <u>1074 S</u> | BE | <u>0.04</u> | CD | <u>0.098</u> | CN | <u><10</u> | CR | <u>1.48</u> |
| | mg/L | | ug/L | | mg/L | | mg/L | | ug/L | | mg/L |
| CR_HEX | <u><0.001</u> | CU | <u>3.85</u> | HG | <u>1.4</u> | NI | <u>2.33</u> | PB | <u>5.4</u> | SB | <u><1 S</u> |
| | mg/L | | mg/L | | ug/L | | mg/L | | mg/L | | ug/L |
| SE_HY | <u>14.8 S</u> | TL | <u>1.23</u> | ZN | <u>11.0</u> | | | | | | |
| | ug/L | | mg/L | | mg/L | | | | | | |

| | | | |
|---------------------------------|--------------|--|----------------|
| SAMPLE ID <u>B-201 SEDIMENT</u> | | SAMPLE # <u>03</u> FRACTIONS: <u>A</u> | |
| | | Date & Time Collected <u>12/06/89</u> | Category _____ |
| TOC_S | <u>11900</u> | | |
| | mg/Kg | | |

| | | | | | | | | | | | |
|-------------------------------|------------------|-------|--------------|--|-----------------|----------------|--------------|----|------------|----|--------------|
| SAMPLE ID <u>B-202 TIME 0</u> | | | | SAMPLE # <u>04</u> FRACTIONS: <u>A,B,C,D</u> | | | | | | | |
| | | | | Date & Time Collected <u>12/08/89</u> | | Category _____ | | | | | |
| AG | <u>0.043 E</u> | AS_HY | <u>212 S</u> | BE | <u><0.02</u> | CD | <u>0.054</u> | CN | <u>104</u> | CR | <u>0.449</u> |
| | mg/L | | ug/L | | mg/L | | mg/L | | ug/L | | mg/L |
| CR_HEX | <u><0.001</u> | CU | <u>4.73</u> | HG | <u>6.9</u> | NI | <u>1.39</u> | PB | <u>3.3</u> | SB | <u>3.0 S</u> |
| | mg/L | | mg/L | | ug/L | | mg/L | | mg/L | | ug/L |

Page 3
Received: 12/07/89

RADIAN CORP.
Results by Sample

Work Order # M9-12-017
Continued From Above

SE_HY 8.2 S TL <0.06 ZN 16.4 D
ug/L mg/L mg/L

SAMPLE ID B-202 TIME 15 SLURRY SAMPLE # 05 FRACTIONS: A,B,C,D
Date & Time Collected 12/08/89 12:00:00 Category
AG 0.034 E AS_HY 216 S BE <0.02 CD 0.064 CN 93 CR 0.501
mg/L ug/L mg/L mg/L ug/L mg/L
CR_HEX <0.001 CU 5.12 HG 8.4 NI 1.47 PB 3.7 SB 2.3 S
mg/L mg/L ug/L mg/L mg/L ug/L ug/L
SE_HY 9.3 S TL <0.06 ZN 18.3 D
ug/L mg/L mg/L

SAMPLE ID B-202 SEDIMENT SAMPLE # 06 FRACTIONS: A
Date & Time Collected 12/06/89 Category
TOC_S 1190
mg/Kg

SAMPLE ID B-203 TIME 0 SLURRY SAMPLE # 07 FRACTIONS: A,B,C,D
Date & Time Collected 12/08/89 12:00:00 Category
AG 0.069 E AS_HY 478 S BE 0.04 CD 0.104 CN 81 CR 0.735
mg/L ug/L mg/L mg/L ug/L mg/L
CR_HEX <0.001 CU 9.12 HG 14.6 NI 2.00 PB 11 D SB 8.0 S
mg/L mg/L ug/L mg/L mg/L ug/L ug/L
SE_HY 17.9 S TL 0.20 ZN 35.0 D
ug/L mg/L mg/L

Page 4
Received: 12/07/89

RADIAN CORP.

REPORT

Work Order # M9-12-017

Results by Sample

| | | | | | | | | | | | |
|---------------------------------------|------------------|-------|--------------|--------------------|---------------|---------------------------|--------------|--|-------------|----------------|--------------|
| SAMPLE ID <u>B-203 TIME 15 SLURRY</u> | | | | SAMPLE # <u>08</u> | | FRACTIONS: <u>A,B,C,D</u> | | Date & Time Collected <u>12/08/89 12:00:00</u> | | Category _____ | |
| AG | <u>0.067 E</u> | AS_HY | <u>448 S</u> | BE | <u>0.04</u> | CD | <u>0.104</u> | CN | <u>74</u> | CR | <u>0.695</u> |
| | mg/L | | ug/L | | mg/L | | mg/L | | ug/L | | mg/L |
| CR_HEX | <u><0.001</u> | CU | <u>9.24</u> | HG | <u>38.4</u> | NI | <u>2.07</u> | PB | <u>11 D</u> | SB | <u>6.5 S</u> |
| | mg/L | | mg/L | | ug/L | | mg/L | | mg/L | | ug/L |
| SE_HY | <u>25.2 S</u> | TL | <u>0.19</u> | ZN | <u>35.2 D</u> | | | | | | |
| | ug/L | | mg/L | | mg/L | | | | | | |

| | | | | | | | | | |
|---------------------------------|--|--------------------|--|---------------------|--|---------------------------------------|--|----------------|--|
| SAMPLE ID <u>B-203 SEDIMENT</u> | | SAMPLE # <u>09</u> | | FRACTIONS: <u>A</u> | | Date & Time Collected <u>12/06/89</u> | | Category _____ | |
| TOC_S <u>2530</u> | | | | | | | | | |
| mg/Kg | | | | | | | | | |

| | | | | | | | | | | | |
|--------------------------------------|------------------|-------|---------------|--------------------|--------------|---------------------------|---------------|--|---------------|----------------|---------------|
| SAMPLE ID <u>B-204 TIME 0 SLURRY</u> | | | | SAMPLE # <u>10</u> | | FRACTIONS: <u>A,B,C,D</u> | | Date & Time Collected <u>12/08/89 12:00:00</u> | | Category _____ | |
| AG | <u>0.390 E</u> | AS_HY | <u>1560 S</u> | BE | <u>0.10</u> | CD | <u>0.951</u> | CN | <u>1450 E</u> | CR | <u>5.19</u> |
| | mg/L | | ug/L | | mg/L | | mg/L | | ug/L | | mg/L |
| CR_HEX | <u><0.001</u> | CU | <u>59.9 D</u> | HG | <u>235.0</u> | NI | <u>14.5 D</u> | PB | <u>68 D</u> | SB | <u>43.5 S</u> |
| | mg/L | | mg/L | | ug/L | | mg/L | | mg/L | | ug/L |
| SE_HY | <u>138 S</u> | TL | <u>1.12</u> | ZN | <u>137 D</u> | | | | | | |
| | ug/L | | mg/L | | mg/L | | | | | | |

| | | | | | | | | | | | |
|---------------------------------------|------------------|-------|---------------|--------------------|-------------|---------------------------|---------------|--|-------------|----------------|---------------|
| SAMPLE ID <u>B-204 TIME 15 SLURRY</u> | | | | SAMPLE # <u>11</u> | | FRACTIONS: <u>A,B,C,D</u> | | Date & Time Collected <u>12/08/89 12:00:00</u> | | Category _____ | |
| AG | <u>0.429 E</u> | AS_HY | <u>2370 S</u> | BE | <u>0.10</u> | CD | <u>1.22</u> | CN | <u>580</u> | CR | <u>6.10</u> |
| | mg/L | | ug/L | | mg/L | | mg/L | | ug/L | | mg/L |
| CR_HEX | <u><0.001</u> | CU | <u>85.1 D</u> | HG | <u>99.0</u> | NI | <u>23.2 D</u> | PB | <u>50 D</u> | SB | <u>70.2 S</u> |
| | mg/L | | mg/L | | ug/L | | mg/L | | mg/L | | ug/L |

Page 5

Received: 12/07/89

RADIAN CORP.

REPORT

Work Order # M9-12-017

Results by Sample

Continued From Above

SE_HY 147 S TL 1.24 ZN 195 D
ug/L mg/L mg/L

SAMPLE ID B-204 SEDIMENT

SAMPLE # 12 FRACTIONS: A

Date & Time Collected 12/05/89

Category

TOC_S 12300
mg/Kg

Page 6

RADIAN CORP.

REPORT

Work Order # M9-12-017

Received: 12/07/89

12/28/89 10:25:17

STS CONSULTANTS, LTD

CYANIDE:

N\A = RESULT NOT AVAILABLE DUE TO CHANGE IN PHYSICAL STATE OF SAMPLE ON
ACIDIFICATION FOR CYANIDE ANALYSIS.

E = ESTIMATED RESULT DUE TO CHANGE IN PHYSICAL STATE OF SAMPLE ON ACIDIFICATION
DURING CYANIDE ANALYSIS.

METALS:

S = EXPLANATION IN APPENDIX.

D = EXPLANATION IN APPENDIX.

Page 7

Received: 12/07/89

RADIAN CORP.

REPORT

Work Order # M9-12-017

NonReported Work

FRACTION AND TEST CODES FOR WORK NOT REPORTED ELSEWHERE

| | | | | |
|-----|--------|-----|--|-------|
| 01D | DIG_N | 01A | | TREAT |
| 02D | DIG_N | | | |
| 03A | SUBCON | | | |
| 04D | DIG_N | 04A | | TREAT |
| 05D | DIG_N | | | |
| 06A | SUBCON | | | |
| 07D | DIG_N | 07A | | TREAT |
| 08D | DIG_N | | | |
| 09A | SUBCON | | | |
| 10D | DIG_N | 10A | | TREAT |
| 11D | DIG_N | | | |
| 12A | SUBCON | | | |

Appendix A

Comments, Notes and Definitions

Notes and Definitions

* Est. result less than 5 times detection limit
A Analytical and/or post-digestion spike
B Detected in blank, result not corrected
C Confirmed on second column
D Sample diluted for this analyte
E Estimated result - see report narrative
G Exceeds calibration range
J Detected at less than detection limit
NA Not analyzed
NC Not calculated
ND Not detected at specified detection limit
NR Analyte not requested
NS Not spiked
N/A Not available
P Previously confirmed
Q Outside control limits
R Detected in blank, result corrected
S Determined by Method of Standard Addition
U Unconfirmed-2nd column not requested
X Not confirmed by analysis on 2nd column

Notes and Definitions

Page: A

- * The asterisk(*) is used to flag results which are less than five times the method specified detection limit. Studies have shown that the uncertainty of the analysis will increase exponentially as the method detection limit is approached. These results should be considered approximate.
- A This flag indicates that a spike is an analytical and/or post-digestion spike. These spikes have not been subjected to the extraction or digestion step.
- B This flag indicates that the analyte was detected in the reagent blank but the sample results are not corrected for the amount in the blank.
- C Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The C flag indicates that the analyte has been confirmed by analysis on a second column.
- D This flag identifies all analytes identified in analysis at a secondary dilution factor. In an analysis some compounds can exceed the calibration range of the instrument. Therefore two analyses are performed, one at the concentration of the majority of the analytes, and a second with the sample diluted so that high concentration analyte(s) fall within the calibration range.

Notes and Definitions

Page A

E

The reported value is estimated because of the presence of interference. The potential source of the interference is included in the report narrative.

G

This flag identifies a GC/MS result whose concentration exceeds the calibration range for that specific analysis. Usually if one or more compounds have a response greater than full scale, the sample or extract is diluted and re-analyzed.

J

Indicates an estimated value for GC/MS data. This flag is used either when estimating a concentration for tentatively identified compounds where a response factor of 1 is assumed, or when the mass spectral data indicate the presence of a compound that meets the identification criteria but the result is less than the sample quantitation limit.

NA This analyte was not analyzed.

NC

Applies to RPD and spike recovery results. The relative percent difference (RPD) and spike recovery are not calculated when a result value is less than five times the detection limit or obvious matrix interferences are present. See * definition for further explanation of the unreliability of data near the detection limit. A spike recovery is not calculated when the sample result is greater than four times the spike added concentration because the spike added concentration is considered insignificant.

Notes and Definitions

ND

This flag (or <) is used to denote analytes which are not detected at or above the specified detection limit. The value to the right of the < symbol is the method specified detection limit for the sample.

NR This analyte was not requested by the client.

NS This analyte or surrogate was not added (spiked) to the sample for this analysis.

N/A A result or value is not available for this parameter, usually a detection limit.

P Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The P flag indicates that the analyte has been confirmed previously. This flag is applicable to analyses of samples arising from a regular sampling program as a specific sample source; for example, a quarterly well monitoring program.

Notes and Definitions

Page A-6

- Q This quality control standard is outside method or laboratory specified control limits. This flag is applied to matrix spike, analytical QC spike, and surrogate recoveries; and to RPD(relative percent difference) values for duplicate analyses and matrix spike/matrix spike duplicate result.
- R This flag indicates that the analyte was detected in the reagent blank and the sample results are corrected for the amount in the blank.
- S This flag indicates that a specific result from a metals analysis has been obtained using the Method of Standard Addition.
- U Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The U flag indicates that second column was not requested.
- X Most methods of analysis by gas chromatography recommend reanalysis on a second column of dissimilar phase to resolve compounds of interest from interferences that may occur and for analyte confirmation. The X flag indicates a second column confirmation was performed but the analyte was not confirmed and is likely a false positive.

Notes and Definitions

Page A-7

TERMS USED IN THIS REPORT:

Analyte - A chemical for which a sample is to be analyzed. The analysis will meet EPA method and QC specifications.

Compound - See Analyte.

Detection Limit - The method specified detection limit, which is the lower limit of quantitation specified by EPA for a method. Radian staff regularly assess their laboratories' method detection limits to verify that they meet or are lower than those specified by EPA. Detection limits which are higher than method limits are based on experimental values at the 99% confidence level. Note, the detection limit may vary from that specified by EPA based on sample size, dilution or cleanup.
(Refer to Factor, below)

EPA Method - The EPA specified method used to perform an analysis. EPA has specified standard methods for analysis of environmental samples. Radian will perform its analyses and accompanying QC tests in conformance with EPA methods unless otherwise specified.

Factor - Default method detection limits are based on analysis of clean water samples. A factor is required to calculate sample specific detection limits based on alternate matrices (soil or water), use of cleanup procedures, or dilution of extracts/digestates. For example, extraction or digestion of 10 grams of soil in contrast to 1 liter of water will result in a factor of 100.

Matrix - The sample material. Generally, it will be soil, water, air, oil, or solid waste.

Radian Work Order - The unique Radian identification code assigned to the samples reported in the analytical summary.

| | |
|--------------|---|
| Units - ug/L | micrograms per liter (parts per billion); liquids/water |
| ug/Kg | micrograms per kilogram (parts per billion); soils/solids |
| ug/M3 | micrograms per cubic meter; air samples |
| mg/L | milligrams per liter (parts per million); liquids/water |
| mg/Kg | milligrams per kilogram (parts per million); soils/solids |
| % | percent; usually used for percent recovery of QC standards |
| uS/cm | conductance unit; microSiemens/centimeter |
| mL/hr | milliliters per hour; rate of settlement of matter in water |
| NTU | turbidity unit; nephelometric turbidity unit |
| CU | color unit; equal to 1 mg/L of chloroplatinate salt |